

AD-A009 309

EMPLACEMENT AND STEMMING LOAD
MEASUREMENTS; PROJECT CANNIKIN

Donnie L. Ainsworth, et al

Army Engineer Waterways Experiment
Station

Prepared for:

Atomic Energy Commission

March 1975

DISTRIBUTED BY:

NTIS

National Technical Information Service
U. S. DEPARTMENT OF COMMERCE

Destroy this report when no longer needed. Do not return
it to the originator.

ADDITIONAL INFO	
WTS	VER. 1.0
END	DATE 8/10/48
UNCLASSIFIED	<input type="checkbox"/>
DISSEMINATION	<input type="checkbox"/>
BY	
DISSEMINATION/REMARKS	
Dist.	AVAIL. REV. or CHG
A	

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Miscellaneous Paper C-75-1	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER AD-A009309
4. TITLE (and Subtitle) EMPLACEMENT AND STEMMING LOAD MEASUREMENTS; PROJECT CANNIKIN		5. TYPE OF REPORT & PERIOD COVERED Final report
7. AUTHOR(s) Donnie L. Ainsworth Dale Glass		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U. S. Army Engineer Waterways Experiment Station Concrete Laboratory P. O. Box 631, Vicksburg, Miss. 39180		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS Lawrence Livermore Laboratory P. O. Box 808 Livermore, Calif. 94550		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1975
		13. NUMBER OF PAGES 37
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Reproduced by NATIONAL TECHNICAL INFORMATION SERVICE US Department of Commerce Springfield, VA. 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Cannikin (Project) Emplacement Nuclear-explosions Stemming (explosions) Underground explosions		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Waterways Experiment Station (WES) participated in Project CANNIKIN, Amchitka Island, Alaska, during the period of September 1970 to November 1974. Lawrence Livermore Laboratory (LLL), Livermore, California, was provided support with instrumentation and personnel to monitor continuously the emplacement and stemming load for the CANNIKIN nuclear experiment. Three gages were prepared by mounting strain gages on 4-ft-long, 10-3/4-in., P110 pup joint steel casing. Each gage was calibrated in the laboratory by pull-testing to a load in excess (Continued)		

20. ABSTRACT (Continued).

of expected field loads and recording the gage output versus load. During the field operation, pup joint gages were placed in the device emplacement casing string at the following locations below the collar at final seating: 5305 ft, 2970 ft, and 72 ft. After connecting each gage in the casing string, the gage output was monitored as it was lowered downhole. The bottom gage provided critical loading information that was used in determining the rate of lowering of the device through several tight or misaligned areas. All three gages were monitored during the stemming operation providing pertinent information regarding stemming load transferred to device canister and casing string.

ia

THE CONTENTS OF THIS REPORT ARE NOT TO BE
USED FOR ADVERTISING, PUBLICATION, OR
PROMOTIONAL PURPOSES. CITATION OF TRADE
NAMES DOES NOT CONSTITUTE AN OFFICIAL EN-
DORSEMENT OR APPROVAL OF THE USE OF SUCH
COMMERCIAL PRODUCTS.

PREFACE

The work reported herein was conducted by personnel from the Concrete Laboratory of the U. S. Army Engineer Waterways Experiment Station (WES). The work was accomplished on Anchitka Island, Alaska, in connection with Project CANNIKIN. The work was conducted for Lawrence Livermore Laboratory (LLL), Livermore, California, under the sponsorship of the Atomic Energy Commission. It was accomplished during the period of September 1970 to November 1971 under the general supervision of Mr. Bryant Mather, Chief, Concrete Laboratory, and under the direct supervision of Mr. R. V. Tye, Jr., Chief, Engineering Sciences Division, and Billy R. Sullivan, Chief, Engineering Physics Branch. Project Engineer for these measurements was Mr. Donnie L. Ainsworth. This report was prepared by Mr. Ainsworth with the assistance of Mr. Dale Glass.

Directors of WES during this investigation and the preparation and publication of this report were COL Levi A. Brown, CE, BG Ernest D. Peixotto, CE, and COL G. H. Hilt, CE. Technical Director was Mr. F. R. Brown.

Preceding page blank

CONTENTS

	<u>Page</u>
PREFACE	3
CONVERSION FACTORS, U.S. CUSTOMARY TO METRIC (SI)	
UNITS OF MEASUREMENT	5
CHAPTER I: INTRODUCTION	6
1.1 Background	6
1.2 Purpose and Scope	8
CHAPTER II: PROCEDURE	9
2.1 Experimental Method	9
2.1.1 Gage Design	9
2.1.2 Gage Calibration	10
2.2 Instrumentation	11
2.3 Field Installation	11
2.4 Field Measurements	12
CHAPTER III: RESULTS	13
3.1 Instrument and Gage Performance	13
3.2 Discussion of Results	14
CHAPTER IV: CONCLUSIONS AND RECOMMENDATIONS	15
FIGURES 2.1 - 3.2	
TABLE 1	

CONVERSION FACTORS, U. S. CUSTOMARY TO METRIC (SI)
UNITS OF MEASUREMENT

U. S. customary units of measurement used in this report can be converted to metric (SI) units as follows:

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
inches	2.54	centimetres
feet	0.3048	metres
pounds	0.4536	kilograms
pounds, force	4.4482	newtons

CHAPTER 1

INTRODUCTION

1.1 BACKGROUND

Nuclear devices that are placed at large vertical distances below the surface are usually lowered on standard API pipe utilizing a drill rig. Upon reaching final position, the device, cables, etc., are supported by the emplacement casing which is attached to the strongback at the surface. The casing used for lowering the device, electrical cable, and any other hardware in the string usually has a safety factor of three on the yield strength for total downhole load. In general, the casing is pull tested to a load 1-1/2 times the total downhole load.

It has been theorized that all of the stemming material load is not transferred to the casing. As material is added the load on the casing increases but not necessarily proportional to the actual weight of the stemming material. It is believed that the stemming material bridges between the side wall and the casing and, therefore, supports some of the load. However, even though this has been the assumption, the casing is always designed to support a load in excess of total weight of device, casing, cables, and stemming material.

WES was requested by Lawrence Radiation Laboratory (LRL), Livermore, California, in their letter of 16 September 1966, to design and calibrate an experiment for measuring the Project STERLING, Station 1A granular stemming load. Sixteen SR-4 strain gages were mounted around the center of a 3-ft section of standard 9-5/8 in., J55, 40-lb long-thread casing. The gages were connected to form two complete load cell circuits each consisting of four active gages and four temperature compensating gages.

The casing load cells were calibrated and later installed in the 2700-ft casing string 30 ft below the strongback. The indication from the load cells was that approximately 22 percent of the material weight added in the annulus and 48 percent of that added in the 9-5/8-in. casing were transmitted to the casing.

One 7-in.-diameter calibrated strain gaged pup-joint was utilized on project GASBUGGY in November and December 1967. This load cell was calibrated in the laboratory to 360,000 lbf and measured a maximum of 224,000 lb in the field experiment. The pup-joint was located approximately 30 ft below the collar in a 4250-ft casing string. WES did not obtain the actual weight of the material added; therefore, a determination of the percent of stemming material weight transmitted to casing was not accomplished.

Three 9-5/8-in.-diameter calibrated strain gage pup joints were used on project FAULTLESS in January 1968. These were located at 3061 ft, 1498 ft, and 50.7 ft below the collar. The maximum loads recorded were 50,000 lb compression, 151,000 lb tension, and 286,000 lb tension, respectively. The load cells were calibrated in the laboratory to 200,000 lbf both in tension and compression, 220,000 lbf tension, and 340,000 lbf tension, respectively.

Three 10-3/4 in. pup joints were also prepared and calibrated for project ADAGIO; however, the project was cancelled prior to field operation. The pup joints and other associated equipment and hardware were set aside for use on other experiments if applicable.

1.2 PURPOSE AND SCOPE

The work described in this report was accomplished specifically for the purpose of support of the Lawrence Livermore Laboratory (LLL) emplacement and stemming operation for Project CANNIKIN. This report will discuss the pup joint fabrication, calibration, and field installation, as well as the measurements obtained.

CHAPTER II

PROCEDURE

2.1 EXPERIMENTAL METHOD

The Engineering Physics Branch, Concrete Laboratory, USAE Waterways Experiment Station (WES), was requested by Lawrence Livermore Laboratory, Livermore, California, to design an experiment to measure the emplacement and stemming loads at three stations on the emplacement casing for Project CANNIKIN, Amchitka Island, Alaska. Project CANNIKIN was a 5 megaton underground nuclear test detonated in November 1971. The device was positioned approximately 5875 ft beneath the surface and was lowered and supported from the surface by 10-3/4 in. API casing. The 90-in.-diameter borehole was cased with 54-in.-diameter casing.

2.1.1 Gage Design. The gages designed for this work were similar to those used by WES on Projects STERLING, GASBUGGY, and FAULTLESS. Each gage was designed around a 4-ft-long, 10-3/4 in., P-110 pup joint which was to become an integral part of the emplacement casing string. Each gage consisted of 16 wire strain gages mounted around the circumference of the pup joint forming two full four arm temperature compensated bridge networks. Figure 2.1 is a photograph of typical gage installation around the casing. One 4-conductor shielded Belden No. YR 7869 cable was used to provide power to both bridges and another identical cable to monitor outputs.

The strain gages and solder joints were waterproofed with successive applications of Gagekote No. 1, Gagekote No. 5, and Gagekote No. 2.

To protect the gages, connecting wires, and terminals, a dust-tight 20 gage sheet metal shield was installed around the gage area and was held in place by welding to the sleeve installed on the end of the pup joint. The shield was sealed with RTV silastic to prevent dust and moisture from migrating to the gages.

2.1.2 Gage Calibration. The two pup joints for the lower stations weighed 51-lb per ft and the one for the top station weighed 71.1-lb per ft. The two 51-lb per ft strain gaged pup joints were calibrated by pulling to 440,000 lbf with the 440,000-lbf Universal Loading Machine at the WES Concrete Laboratory (CL). Figure 2.2 is a photograph of a pup joint installed in the loading machine. The calibration instrumentation is also shown in this photograph. Figure 2.3 is a photograph of the hardware utilized in the pulling operation.

Calibration data were obtained every 20,000 lbf from 0-400,000 lbf tension and from 0-100,000 lbf compression for the bottom pup joint. Figure 2.4 is a plot of the calibration data load versus bridge output. This plot shows that the load cell has a linear response over the range tested. A similar calibration curve was obtained for the middle pup joint over the range of 0-440,000 lbf tension and is shown in figure 2.5.

The 71.1-lb per ft top pup joint was shipped by LLL to Los Alamos, New Mexico, and was strain gaged and calibrated by WES personnel at the Zia Company facility at Los Alamos. This heavier joint was calibrated to 1,500,000 lbf in the Zia Company's pull testing apparatus. The testing apparatus was operated by Zia personnel. Figure 2.6 is a plot of load versus bridge output for this pup joint.

All three pup joint load cells were calibrated with the cable used in the actual field operation. This alleviates the concern for the effects of long cable lengths on the response of the measuring system. Calibration steps were obtained by shunting known resistances across an active arm of the bridge denoting the bridge output voltage change and relating this change to simulated load. These calibrations are shown in figures 2.4, 2.5, and 2.6.

2.2 Instrumentation. Each full bridge network was powered and conditioned by a Model SAM-1, Sensor Analog Module, manufactured by MB Electronics. The unit contains a 0-25 volt DC transducer power supply, amplifier, and a four step bridge calibrator. The output of the conditioning unit was connected to the input of a Westronic multiple point recorder in parallel with a Model 8100A Fluke digital multimeter.

The bridge power voltage was adjusted to 10 volts for each load cell and the amplifier was adjusted to give a full scale deflection of the recorder for a load in excess of that expected. Full scale deflections were set as follows for the respective load cells: top, 1,000,000 lb; middle, 800,000 lb; and bottom, 500,000 lb.

2.3 Field Installation. The gages were installed in the casing string as follows: the lower pup joint was installed on 14 October 1971 and was located such that at final seating it was approximately 5305 ft below the collar; the middle pup joint was installed on 19 October 1971 at a depth of approximately 2970 ft below the collar; and the top pup joint was installed on 26 October 1971 at a depth of approximately 72 ft below the collar. After the hermetically sealed cable connections were

made near the installed instrumented pup joint, the connectors were coated with an RTV silastic adhesive and wrapped with electrical tape.

2.4 Field Measurements. Because of anticipated long emplacement duration, it was originally planned to begin continuous monitoring of load after the emplacement string was landed on the strongback. However, upon arrival on Amchitka, WES personnel were consulted by Messrs. Petrie and Lake regarding the possibility of using the lower WES pup joint for the additional task of determining the load changes due to friction on the device and diagnostic cannister during the emplacement operation. WES determined that at least a minimum of 500-lb load change could be determined. It was then decided that WES should monitor this channel continuously and maintain intercom contact with the LLL representative in charge of the downhole operation, especially while moving through the critical locations.

CHAPTER III

RESULTS

3.1 INSTRUMENT AND GAGE PERFORMANCE

During the emplacement operation, WES monitored the in-place load cells continuously. One channel of the lower load cell was used to monitor the load change on the cannister. Using a digital multimeter, load changes as little as 10 lb could be observed; however, while the emplacement casing was moving, mechanical vibrations caused dynamic oscillations with amplitudes of several hundred pounds. Utilizing a strip chart continuous recorder, WES personnel were able to detect any instantaneous loading of the device cannister and, thereby, aid in determining the rate of lowering the device through several critical or tight locations. Figure 3.1 is a typical strip chart of load versus time curve.

Both gages at each of the three stations were monitored during the stemming operation. The emplacement casing and device cannister weights recorded prior to stemming were 679,000 lb; 400,000 lb; and 183,000 lb for the top, middle, and bottom load cells, respectively. With the addition of granular stemming material, the lower gage went into compression and continued until a minimum load of 72,000 lb was reached at which time it indicated a constant load for the remainder of the operation. The load on the middle cell remained fairly constant throughout the stemming operation. The load on the top cell increased slowly until gravel was added to 10-3/4 in. pipe at which time the load remained constant until the final stemming with sand was begun. At this time it

increased to a maximum load of 855,000 lb. Loading data taken from the strip chart records are shown in table 1.

3.2 DISCUSSION OF RESULTS

Figure 3.2 is a plot of change in load versus time as determined by the three load cells. As shown on all the curves the load dropped 90,000 to 97,000 lb when the casing was landed on the strongback. Zero load change is taken as the load immediately prior to stemming. Apparently the middle load cell did not measure a significant load change because of bridging of the sand below the middle cell. Some of the drops in loads can be attributed to the collapse of bridging. One noted in particular occurred at about 1200, 2 November 1971. This was noted at the same instant by EG&G personnel. The irregularities in the load curve of the upper load cell after 1100, 4 November 1971, can also be attributed to bridging collapse. The irregularities began occurring with final stemming with pea gravel.

CHAPTER IV


CONCLUSIONS AND RECOMMENDATIONS

The laboratory calibrated strain gaged load cells performed well in the field experiment at depths to 5305 ft. They were utilized in a special situation where a greater sensitivity was required than the original design intended. The WES equipment and personnel played an important part not only in the planned stemming operation but, also, in the downhole emplacement operation.


There was some concern among several LLL personnel that the WES cable was somewhat fragile for this particular experiment. Although no difficulty was encountered, LLL's concern was appreciated. It is, therefore, recommended that larger diameter and stronger cable be used for future operations.



Typical Gage Installation Around Pipe
Fig. 2.1




Instrumented Pup Joint in Loading Machine
Fig. 2.2



Hardware for Pull Testing Pup Joint

Fig. 2.3






Fig. 2.5




Fig. 2.6




Fig. 3.1




Fig. 3.2

5150

PROJECT CUMULATIVE STEERING LOG AND SURVEILLANCE

Date	Time	Top Load Cell		Bottom Load Cell		Weight of Added Steering Material and General Comments
		Total Load	ΔL	Total Load	ΔL	
1971 Oct 14 16 22 23 25 26 27	1045			297	114	Lifted load and set jacks. Immediately prior to re- moving blocks. After removing blocks. Landed on strongback. Began stemming operation. Sand. 4000 5305 8350 11,600
	0730			295.4	112.4	
	1435			292	109	
	0719			290.3	107.3	
	0845			282	99	
	1820			280	97	
	0830	778	+99	277.6	94.6	
	0839	769	+90	286.5	103.5	
	1012	778	+99	285.2	102.2	
		780	+101			
28	1018	780	+101	285.2	102.2	
	1452	679	0	183	0	
	0715	679	0	183	0	
	1315	679	0	183	0	
	1500					
	1745					
	2020	683	+4	181	-2	
	2205					
	0038	684	+5	180	-3	
	0146	685	+6	179	-4	
	0230	686	+7	178	-5	
	0330	687	+8	178	-5	

Load and ΔL in units of 10^3 pounds.

(Continued)

(1 of 2 sheets)

Table 1 (Continued)

SACRED CATHEDRAL IN ST. LOUIS MO. RECONSTRUCTION

Date	Time	Total Load		Change in Load		Total Load		Weight of Added Steaming Material and General Comments
		lb	oz	lb	oz	lb	oz	
Oct 28	0335	688		+9		402		18,550
	0506							
	0545							23,350
	0615	689		+10		402		
	0700	689		+10		402		
	0803	689		+10		402		
	0835							
	0900	689		+10		403		28,550
	1000	690		+11		403		
	1030							
	1100	690		+11		403		33,750
	1200	690		+11		403		
	1240							
	1300	690		+11		403		46,000
	1400	688		+9		401		
	1500	688		+9		400		
	1525							4 cu ft/min
	1600	688		+9		400		
	1700	686		+7		398		
	1800	685		+6		397		
	1900	684		+5		396		
	2000	686		+7		398		
	2100	686		+7		400		
	2200	688		+9		400		
	2300	688		+9		400		

Load and ΔL in units of 10^3 pounds.

(Continued)

Table 1 (Continued)

PROJECT CANNON STREAMING LOAD MEASUREMENTS

Date	Time	Top Load Cell		Middle Load Cell		Bottom Load Cell		Weight of Added Stemming Material and General Comments
		Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
1971								
Oct 28	2400	688	+9	400	0	165	-18	
Oct 29	0100	687	+8	400	0	163	-20	
	Began adding magnetite							
	0200	695	+16	400	0	157.5	-25.5	
	0245	697	+18	401	+1	156	-27	
	0300	697	+18	402	+2	156	-27	
	0400	700	+21	402	+2	154	-29	
	0500	699	+20	402	+2	155	-30	
	0600	699	+20	402	+2	153	-30	
	0700	699	+20	402	+2	153	-30	
	0800	707	+28	402	+2	147.5	-35.5	
	0900	700	+21	402	+2	152	-31	
	1000	705	+26	402	+2	148	-35	
	1038	Stopped with magnetite. Began adding sand.						
	1100	710	+31	402	+2	146	-37	
	1200	700	+21	402	+2	156	-27	
	1300	701	+22	404	+4	160	-23	
	1318							80 ton/hr Shut down
	1400	706	+27	407	+7	161	-22	
	1500	707	+28	407	+7	158	-25	
	1600	707	+28	407	+7	157	-26	
	1640							
	1655							

Load and ΔL in units of 10^3 pounds.

(Continued)

(3 of 10 sheets)

Table 1 (Continued)

PROJECT CANNON STELLING LOAD MEASUREMENTS

Date		Top Load Cell		Middle Load Cell		Bottom Load Cell		Weight of Added Stemming Material and General Comments
Time		Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
Oct 29	1700	707	+28	408	+8	157.5	-25.5	17,300 lb
	1800	709	+30	408	+8	160	-23	
	1821							
	1900	711	+32	408	+8	158	-25	
	2000	710	+31	408	+8	151	-32	
	2006							
	2100	712	+33	408	+8	146	-37	
	2107							
	2200	712	+33	409	+9	136	-47	
	2300	715	+36	412	+12	127	-56	
30	2400	716	+37	414	+14	126	-57	
	0100	716	+37	414	+14	125	-58	
	0200	717	+38	416	+16	124	-59	
	0300	719	+40	417	+17	124	-59	
	0400	720	+41	416	+16	123	-60	
	0500	718	+39	416	+16	125	-60	
	0600	720	+41	418	+18	123	-60	
	0700	720	+41	419	+19	122.8	-60.2	
	0800	725	+46	423	+23	123	-60	
	0900	724	+45	417	+17	123	-60	
Began stemming with pea gravel in 10-3/4 in. pipe								
	0925							
	1000	720	+41	419	+19	120	-63	
	1100	719	+40	418	+18	120	-63	
	1200	719	+40	418	+18	121	-63	

Load and ΔL in units of 10^3 pounds.

(Continued)

(4 of 10 sheets)

Table 1 (Continued)

PROJECT CANNON IN CEMENT AND LEAD MEASUREMENTS

Date	Time	Top Load Cell		Middle Load Cell		Bottom Load Cell		Weight of Added Stemming Material and General Comments
		Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
Oct 30	1300	720	+41	418	+18	122	-63	
	1400	720	+41	418	+18	122	-63	
	1500	720	+41	416	+16	122	-62	
	1600	718	+39	415	+15	122	-62	
	1700	718	+39	416	+16	122	-62	
	1800	718	+39	416	+16	122	-62	
	1900	718	+39	416	+16	122	-62	
	2000	718	+39	416	+16	122	-61	
	2100	718	+39	415	+15	122	-61	
	2200	718	+39	414	+14	122	-61	
31 Change from daylight to standard time	2300	716	+37	414	+14	122	-61	
	2400	715	+36	412	+12	122	-61	
	0100	715	+36	412	+12	122	-61	
	0200	715	+36	412	+12	122	-61	
	0245	Began stemming annulus with pea gravel						
	0300	716	+37	414	+14	122	-61	
	0400	716	+37	415	+15	122	-61	
	0500	718	+39	415	+15	122	-61	
	0600	718	+39	414	+14	122	-61	
	0700	718	+39	414	+14	122	-61	
	0800	718	+39	414	+14	122	-61	
	0900	718	+39	416	+16	122	-61	

Load and ΔL in units of 10^3 pounds.

(Continued)

Table 1 (Continued)

PROLOG CANALIN 5 - TING LOAD MEASUREMENTS

Date	Time	Total Load			AL	Sub Load		Weight of Added Sealing Material and General Comments
		Total Load	IL	VL		Total Load	VL	
Oct 31	1000	718	+39	416	+16	122	-61	Poured plastic plug
	1100	718	+39	418	+18	122	-61	
	1159							
	1200	718	+39	418	+18	122	-61	
	1243							
	1300	718	+39	418	+18	122	-61	
	1340							
	1348							
	1400	718	+39	418	+18	122	-61	
	1500	718	+39	418	+18	122	-61	
Nov 1	1600	718	+39	418	+18	122	-61	
	1700	718	+39	417	+17	122	-60	
	1800	715	+36	414	+14	122	-60	
	1900	712	+33	412	+12	122	-60	
	2000	712	+33	412	+12	122	-60	
	2100	712	+33	412	+12	123	-60	
	2200	712	+33	412	+12	123	-60	
	2300	711	+32	412	+12	123	-60	
	0100	712	+33	413	+13	123	-60	
	0300	711	+32	411	+11	124	-59	
	0500	711	+32	411	+11	124	-59	
	0700	710	+31	411	+11	124	-59	
	0900	710	+31	411	+11	124	-59	
	1100	712	+33	413	+13	123.5	-59.5	

Load and AL in units of 10^3 pounds.

(Continued)

(6 of 10 sheets)

Table 1 (Continued)
PROJECT CANTAIN STEMMING LOGS PLANT RESULTS

Date	Time	Top Load Cell		Bottom Load Cell		Bottom Load Cell		Weight of Added Stemming Material and General Comments
		Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
Nov 1971	1	713	+34	416	+16	124	-59	
		706	+27	408	+8	124	-59	
		703	+24	406	+6	124.8	-58.2	
		703	+24	406	+6	124.8	-58.2	
		703	+24	406	+6	124	-59	
	2	707	+28	409	+9	124	-59	
		709	+30	410	+10	124	-59	
		709	+30	411	+11	124	-59	
		710	+31	411	+11	124.5	-58.5	
		710	+31	412	+12	124.5	-58.5	
	3	710	+31	413	+13	124.5	-58.5	
		712	+33	414	+14	124.5	-58.5	
		712	+33	414	+14	124.5	-58.5	
		712	+33	414	+14	124.5	-58.5	
		698	+19	398	-2	124.5	-58.5	
	Void collapse - EGSG			Lights came on		124	-59	
	Began stemming at ~ 0100	697	+18	397	-3	125	-58	
		702	+23	402	+2	125.5	-57.5	
		707	+28	406	+6	125.5	-57.5	
		709	+30	407	+7	125.5	-57.5	
		708	+29	407	+7	126	-57	
	0200	712	+33	410	+10	126	-57	
	0300	715	+36	414	+14	126	-57	

Load and ΔL in units of 10³ pounds.

(Continued)

(7 of 10 sheets)

Table 1 (Continued)

PROBABLE CEMENTS DURING 1970 RECONSTRUCTION

Date	Time	Top Load Cell		Middle Load Cell		Bottom Load Cell		Weight of Added Storing Material and General Comments
		Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
Nov 3	0400	715	+36	415	+15	126	-57	
	0500	718	+38	416	+16	126	-57	
	0600	718	+39	416	+16	126	-57	
	0700	720	+41	421	+21	126	-57	
	0800	722	+48	423	+23	126	-57	
	0900	726	+47	426	+26	126	-57	
	1000	729	+50	430	+30	126.5	-56.5	
	1100	729	+50	430	+30	126.5	-56.5	
	1200	730	+51	430	+30	126.5	-56.5	
	1300	734	+55	433	+33	126.5	-56.5	
	1410	736	+57	438	+38	127	-56	
	1500	738	+59	438	+38	126	-57	
	1600	740	+61	438	+38	126	-57	
	1700	741	+62	414	+14	126	-57	
	1800	748	+69	400	0	126	-57	
	1900	750	+71	396	-4	126	-57	
	2000	752	+73	396	-4	126	-57	
	2100	755	+76	396	-4	126	-57	
4	2200	759	+80	396	-4	126	-57	
	2300	761	+82	395	-5	126	-57	
	2400	761	+82	395	-5	126	-57	
	0100	765	+86	395	-5	126	-57	
	0200	768	+89	395	-5	126	-57	
	0300	775	+96	395	-5	126	-57	
	0400	781	+102	395	-5	126	-57	
	0500	781	+102	395	-5	126	-57	

Load and ΔL in units of 10^3 pounds.

(Continued)

(8 of 10 sheets)

Table 1 (Continued)

PROJECT CANTON SPENDING LOAD MEASUREMENTS

Date	Top Load Cell		Middle Load Cell		Bottom Load Cell		Weight of Added Stemming Material and General Comments
	Total Load	ΔL	Total Load	ΔL	Total Load	ΔL	
1971							
Nov 4	0600	+103	395		126	-57	
	0700	+107	395		126	-57	
	0800	+112	395		126	-57	
	0900	+116	395		126	-57	
	1000	+119	395		126	-57	
	1100	+124	395		126	-57	
Began stemming with pea gravel							
	1200	+119	395		126	-57	
	1215	+111					
	1230	+113					
	1245	+101					
	1252	+96					
	1300	+99	394	-6	126	-57	
	1400	+123	394	-6	126	-57	
	1430	+131					
	1445	+134					
	1500	+123	395	-5	126.5	-56.5	
	1515	+116					
	1530	+123					
	1600	+135	395	-5	126.5	-56.5	
	1700	+159	394	-6	126.5	-56.5	
	1800	+175	393	-7	126.5	-56.5	
	1900	+163	393	-7	126.5	-56.5	
	2000	+146	393	-7	126.5	-56.5	
	2100	+136	393	-7	127	-56	

Load and ΔL in units of 10³ pounds.

(Continued)

(9 of 10 sheets)

Table 1 (Concluded)
PROJECT CANNIKIN STENDING LOAD MEASUREMENTS

Date	Time	Top Load Cell		Bottom Load Cell		Weight of Added Steaming Material and General Comments	
		Total Load	ΔL	Total Load	ΔL		
Nov 4	2200	822	+143	393	-7	127	-56
	2300	819	+140	396	-4	127	-56
5	2400	824	+145	397	-3	127	-56
	0100	832	+153	397	-3	127	-56
	0200	822	+143	398	-2	127	-56
	0300	828	+149	402	+2	127	-56
	0400	822	+143	400	0	127	-56
	0500	792	+113	400	0	127	-56
	0600	813	+134	401	+1	127	-56
	0700	828	+149	398	-2	127	-56
	0800	838	+159	398	-2	127	-56
	0930	806	+127	398	-2	127	-56
35	1000	826	+147	397	-3	127	-56
	1100	836	+157	397	-3	127	-56
	1124	830	+151				
	1133	768	+89				
	1200	799	+120	397	-3	127	-56
	1300	837	+158	397	-3	127	-56
	1400	805	+126	397	-3	127	-56
	1500	790	+111	397	-3	127	-56
	1515	791	+112	397	-3	127	-56

Load and ΔL in units of 10^3 pounds.

In accordance with ER 70-2-3, paragraph 6c(1)(b), dated 15 February 1973, a facsimile catalog card in Library of Congress format is reproduced below.

Ainsworth, Donnie L

Emplacement and stemming load measurements; Project Cannikin, by Donnie L. Ainsworth and Dale Glass. Vicksburg, U. S. Army Engineer Waterways Experiment Station, 1975.

1 v. (various pagings) illus. 27 cm. (U. S. Waterways Experiment Station. Miscellaneous paper C-75-1)

Prepared for Lawrence Livermore Laboratory, Livermore, California.

1. Cannikin (Project). 2. Emplacement. 3. Nuclear-explosions. 4. Stemming (explosions). 5. Underground explosions. I. Glass, Dale, joint author. II. California. University. Lawrence Livermore Laboratory. (Series: U. S. Waterways Experiment Station, Vicksburg, Miss. Miscellaneous paper C-75-1)
TA7.W34m no.C-75-1